# Daily Deployments of Ground Network Antennas at Scale Using Commercial Tools

# **Overview and Motivation**

This poster presents KSAT's in-house solution for ground station deployments, configurations and checkout at large scales for multi-mission antennas. RORBUA (Rolling Out Reliably By Unified Architecture) is an Infrastructure as Code solution, streamlining deployment and upgrades of our global network. Mari Linnerud¹\*, Kristian Mikalsen¹, Nikolai Kjærem Ellingsen¹



<sup>1</sup>GN Products, Kongsberg Satellite Services (KSAT) \*mari.linnerud@ksat.no


## PROBLEM STATEMENT

## Background


- Opportunity window for deployment shorter than 15 minutes for busiest antennas
- Automation reduces deployment from months to hours
- Customization requires weeks of preparations
- 100+ antennas with common components in the software stack

### Goals

- Streamline deployment
- Offer common, configurable IaC for all antennas
- Automatic checkout
- Minimize downtime
- Trackable deployment
- Homogenize antenna backends, simplify operations




#### **OVERVIEW OF RORBUA**




- Ansible Tower + Terraform running on VM from headquaters
- Execution node on site to reduce latency
- Caching configurations and docker images on site
- Report antenna status to PagerDuty

#### **AUTOMATED BOOTSTRAP + FIRST DEPLOYMENT**



#### **EXAMPLE: TIMELINE OF DEPLOYMENT ON SINGLE ANTENNA**



Results		
	New standard antenna server	Upgrade
No automation	Months	Days
Automation w/ terraform + Ansible	Days to weeks	Hours
Configurable IaC	Hours to Days (no vs various degree of customization)	Minutes to hours (i.e Svalbard vs Troll)

# **SUMMARY**

- Terraform creates standard bare minimum VM
- Ansible Execution nodes reduces deployment time
- Ansible Inventories gives seamless customizations to deployments
- Gitlab < > Ansible sync version control
- Full overview of deployment history in PagerDuty

